

TENDER SUMMARY: The Priory, Ware

	Description	Price/Costs
1	<i>Site Protection and Signage (see Part 1 of this specification)</i>	£
2	<i>Drain down of all plant after investigation and marking of all flow and return outlets to all emitters throughout. Approximately 54 radiators.</i>	£
3	<i>Removal of existing Heating plant within plant room as described in part 2 of this specification.</i>	£
4	<i>Decorate Plant Room Throughout.</i>	£
5	<i>Supply and installation of new gas fired boiler cascade from Vaillant.</i>	£
6	<i>Supply and installation of new flue system</i>	£
7	<i>Supply & installation of all new distribution pipework within plant room.</i>	£
8	<i>Installation of 2 x pressurisation units and expansion vessels for heating system.</i>	£

9	<i>Supply and installation of new associated controls and wiring.</i>	£
10	<i>Full flush of all heating circuits (54 Rads).</i>	£
11	<i>Supply and installation of new IMI-Hydronics eclipse TRV's throughout. TRV's must be installed to flow pipework.</i>	£
12	<i>Supply and installation of Smiths Environmental MHR unit.</i>	£
13	<i>Full Commissioning.</i>	£
14	<i>Supply of O&M's.</i>	£
15	<i>Supply of written maintenance proposal contract.</i>	£0.00
16	<i>Remove all debris and rubbish from site</i>	£
17	<i>Plant room valve chart</i>	£
TOTAL:		£